



# SHALEDRILLER 205

# **DRAWWORKS**

1,500 HP ICD Drawworks powered by (1) 1,500 HP AC Motor

# MAST AND SUBSTRUCTURE

ICD Hydraulically Raised Mast: 143' Height, 750,000 lbs. Static Hook Load ICD Hydraulically Raised "Single Load" Substructure: 26' Height, 22'-5 ¾" Clear Height Setback Capacity: 500,000 lbs. Racking Capacity: 20,000' (5" Drill Pipe) Fully integrated, omnidirectional "Walking" System Telescoping Flow Line custom engineered for multi-well walking applications

#### **MUD PUMPS**

(3) 1,600 HP Triplex Pumps - 7,500psi (1) each 1,500 HP AC Motor

# **ROTATING AND TRAVELING EQUIPMENT**

500 ton NOV TDS-11SA Top Drive w/ 37,500 ft-lbs. torque @ 110 rpm 37-1/2" Rotary Table Independent Drive powered by (1) Hydraulic Motor (rotary not suited for drilling application "false rotary") 400 ton Traveling Block

# **B.O.P EQUIPMENT**

BOP Handling System: Trolly Beam System w/ Air Winches 13-5/8" x 5,000 psi Annular 13-5/8" x 10,000 psi, Single Ram BOP 13-5/8" x 10,000 psi, Double Ram BOP 2-1/16" X 4-1/16" 10,000 psi Choke Manifold (1) 6 Station Accumulator Skid

### **GENERATORS**

(3) Cummins QSK50 Diesel Engines w/ (3) 1750 kVa Generator Sets(3) Hythane Bi-Fuel (natural gas/diesel) package (1 per engine)

#### **CONTROL SYSTEM**

Precise (OMRON) VFD House Climate Control Driller's Cabin w/ joystick controls





# SHALEDRILLER 205 (continued)

#### **MUD SYSTEM**

1000 bbl. Pit System - 7,500 psi

(2) Derrick Hyperpool Shale Shakers

(1) Derrick 16 Cone Desilter

(1) Derrick 3 Cone Desander

(1) Derrick Vacu-Flo 1,200 Vacuum Degasser

(1) Mud Gas Separator 1,200 gpm 48" diameter / 16' overall length

All solids Control Equipment mount on a one load hydraulically raised equipment skid

#### MUD MIXING EQUIPMENT

(2) Chemical Mixing Hoppers on a single skid(1) Caustic Mixing System

### LIQUID STORAGE

(1) 500 bbl. Water Storage Tank
(1) 500 bbl. Diesel Storage Tank

### PIPE HANDLING EQUIPMENT

NOV ST-80C Iron Roughneck
Canrig Hydraulic Catwalk

### ELECTRONIC DRILLING RECORDING EQUIPMENT

MD Totco Recording System and Equipment

# **DRILL PIPE**

20,000' - 5" (S-135) 19.50# w/ NC-50 Connections (30) Joints - 5" HWDP

#### **DRILL COLLARS**

(18) 6.5" w/ NC-46 Connections (6) 8" w/ NC-56 Connections

# LIVING QUARTERS

- (1) Rig Manager Trailer
- (2) Twelve Person Crew Trailers
- (1) Change House—washer, dryer and crew lockers