



SHALEDRILLER 322

DRAWWORKS

2,000 HP NOV Drawworks powered by (1) 2,000 HP AC Motor

MAST AND SUBSTRUCTURE

Two (2) Section Mast: 142' Height, 750,000 lbs. Static Hook Load Hydraulically Raised Substructure: 25' Height, 22'-6" Clear Height

Setback Capacity: 650,000 lbs.

Racking Capacity: 25,000' (5" Drill Pipe)

Fully integrated, omnidirectional, "Walking" system

MUD PUMPS

(3) 1,600 HP Triplex Pumps - 7,500psi DC Pumps integrated w/ NOV Amphion AC Control System

ROTATING AND TRAVELING EQUIPMENT

500 ton NOVTDS-11SHTop Drive w/ 51,000 ft-lbs. torque @ 110 rpm 37-1/2" Rotary Table Independent Drive powered by (1) DC Motor 500 ton Traveling Block

B.O.P EQUIPMENT

BOP Handling System: Trolly Beam System w/ Hydraulic Winches

13-5/8" x 5,000 psi Annular

13-5/8" x 10,000 psi, Single Ram BOP

13-5/8" x 10,000 psi, Double Ram BOP

2-1/16" X 4-1/16" 10,000 psi Choke Manifold

(1) 7 Station Accumulator Skid

GENERATORS

(4) CAT 3512C Diesel Engines w/ (4) 1750 kVa Generator Sets

CONTROL SYSTEM

NOV Amphion VFD House Climate Control Driller's Cabin w/ joystick controls



MUD SYSTEM



SHALEDRILLER 322 (continued)

1000 bbl. Pit System - 7,500 psi (3) Derrick Hyperpool Shale Shakers (1) Brandt 20 Cone Desilter (1) Brandt 3 Cone Desander (1) Brandt Vacuum Degasser (1) Mud Gas Separator 1,200 gpm 48" diameter / 14'-10" overall length MUD MIXING EQUIPMENT (1) Chemical Mixing Hopper (1) Caustic Mixing System LIQUID STORAGE (1) 500 bbl. Water Storage Tank (1) 500 bbl. Diesel Storage Tank PIPE HANDLING EQUIPMENT (1) NOV ST-80C Iron Roughneck (1) Forum Hydraulic Catwalk

DRILL PIPE

25,000' - 5" (S-135) 19.50# w/ NC-50 Connections (30) Joints - 5" HWDP

MD Totco Recording System and Equipment

ELECTRONIC DRILLING RECORDING EQUIPMENT

DRILL COLLARS

(18) 6.5" w/ NC-46 Connections (6) 8" w/ NC-56 Connections

LIVING QUARTERS

- (1) Rig Manager Trailer
- (2) Twelve Person Crew Trailers
- (1) Change House—washer, dryer and crew lockers